	19th Cross roads			1	120.00	1.00		120.00		
	12th cross			1	130.00	1.00		130.00		
	20th cross			1	1020.00	1.00		1020.00		
							Total	1270.00	268.92	341528.00
	Basic Rate	249.00								
	Area Weightage 8%	19.92								
	Total	268.92								
4	KSRRB 500-7: Providing and applying tack coat on the prepared black topped surfaces at 5kg per 10 sqm, heating bitumen in boiler fitted with spray set (Excluding cleaning of road surface) including cost of all Materials, labour, HOM of machineries complete as per specifications. MORTH Chapter 5 **Page No. 176/ Item No. 21.8/ PWD SR 2013-14**	Sqm								
	19th Cross roads			1	120.00	1.00		120.00		
	12th cross			1	130.00	1.00		130.00		
	20th cross & Cross roads			1	1020.00	1.00		1020.00		
								1270.00	21.71	27572.00
	Basic Rate	20.10								
	Area Weightage 8%	1.61								
	Total	21.71								
5	KSRRB M500-17: Providing and laying **semi dense bituminous concrete 25mm thick** with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH Specification clause No. 500.8 complete in all respects as per specifications. With 80/100 grade bitumen using 40-60 HMP using Mechanical paver **Page No. 178/ Item No. 21.20.5/ PWD SR 2013-14**	Cum								
	19th Cross roads		1	120.00	3.00	0.025	9.00			
	12th cross		1	130.00	3.00	0.025	9.75			
	20th cross		1	1020.00	3.00	0.025	76.50			
	Ugd line		1	120.00	1.00	0.025	3.00			
			1	130.00	1.00	0.025	3.25			
			1	1020.00	1.00	0.025	25.50			
							95.25	9794.52	932928	
	Basic Rate	9069.00								
	Area Weightage 8%	725.52								
	Total	9794.52								
6	Carriage of Mixed Materials Page No. 186 Note PWD SR 2013-14				Qty item no.5			95.25	52.11	4963.0
	1st to2ndKM	5.75								
	2nd-5th KM	16.50								
	5th -10th KM	26.00								
		48.25								
	Area Weightage 8%	3.86								
	Total	52.11								
7	Removing B.S.Slab of drain and stacking etc., complete Page No. 28/ Item No. 5.32/ PWD SR 2013-14	Sqm								
	12th cross		1	180.00	0.90			162.00		
			Consider 60% Qty					97.20		
								97.20	50.11	4871